

不 5-9 汚水枝線舗装復旧工事（1 5 その 8）数量計算書

数 量 総 括 表									
工事区分	工 種	種 別	細 別	規 格	単位	数 量	数値	設計数量	摘 要
道路維持									
	舗装工				式				
		舗装打換え工			式				
			舗装版切断	t=15cm以下（5cm）	m	51.40	1	51	
			舗装版破碎	t=15cm以下	m2	1787.74	10	1790	
			切断濁水運搬処分		m3	0.07	1	0.07	
			殻運搬処分	t=15cm以下 Asガラ、掘削積込み	m3	89.39	1	89	
			不陸整正		m2	1787.74	10	1790	
			補足材（RM-40）		m3	7.14	1	7	
			再生密粒度アスコン（13）						
			表層	PK-3, t=5cm	m2	1787.74	10	1790	
	区画線工				式				
			溶融式区画線	実線 15cm 黄	m	15.20	1	15	
			溶融式区画線	実線 30cm 白	m	2.70	1	3	
			溶融式区画線	破線 45cm 白	m	1.50	1	2	
			溶融式区画線	セブラ 45cm 白	m	8.38	1	8	
			溶融式区画線	文字 15cm換算 白	m	64.74	1	65	
		交通誘導警備員			式				
			交通誘導警備員	交通誘導警備員 B	人	21.00	1	21	

数量集計

工種	規格	計算書	合計	単位	備考
舗装版 切断	t=15cm以下 (t=5cm)	51.40 =	51.40	m	
	計		51.40	m	
舗装版 切断 濁水処分	t=5cm	51.40 × 0.130 ÷ 100 =	0.07	m3	
	計		0.07	m3	
舗装版 撤去	舗装版破碎 t=15cm以下	1787.74 =	1787.74	m2	
	計		1787.74	m2	
舗装版 殻処分	t=15cm以下 (t=5cm)破碎	m2 t 1787.74 × 0.05	89.39	m3	
	計		89.39	m3	
不陸整正		1787.74 =	1787.74	m2	
	計		1787.74	m2	
	補足材 (RM-40) t = 2cm	281.13 × 0.02 × 1.27	7.14	m3	
舗装	再生密粒度アスコン (13)	1787.74 =	1787.74	m2	
	計		1787.74	m2	
区画線		1.1*1.1 消火栓 箇所			
	実線・15cm・黄	3.80 × 4.00 =	15.20	m	
		150+(150-30) 十字			
	実線・30cm・白	2.70 =	2.70	m	
		0.5×3 指導停止線			
	破線・45cm・白	1.50	1.50	m	
		3.2~0.15 (5本) 横断歩道			
区画線	ゼブラ・45cm・白	8.38	8.38	m	
		120×200 注意通学路			
	文字・15cm換算・白	40.20 + 12.27 × 2 =	64.74	m	
	計		92.52	m	

鋪 装													
NO	面積								鋪装版切断			補足材	備考
	L	W1	W2	— W	小計	人孔蓋控除 (Φ600)		計				RM-40 t =2	
	m	m	m	m	m2	個	0.28m2/個	m2	m	m	m	m2	
1	4.10	9.90	2.60	6.25	25.63	1	(0.28)	25.35	9.90	6.00	5.20		
2	0.80	0.00	3.00	1.50	1.20		0.00	1.20					
3	13.20	3.00	2.56	2.78	36.70	1	(0.28)	36.42					
4	7.40	2.56	3.00	2.78	20.57		0.00	20.57					
5	21.01	3.00	2.90	2.95	61.98		0.00	61.98					
6	2.90	1.20	1.80	1.50	4.35	1	(0.28)	4.07					
7	21.40	3.10	3.08	3.09	66.13		0.00	66.13					
8	1.40	3.08	2.80	2.94	4.12	1	(0.28)	3.84					消火栓
9	11.20	2.80	2.94	2.87	32.14		0.00	32.14					
10	5.00	2.94	2.80	2.87	14.35		0.00	14.35	5.00				
11	1.00	2.80	0.00	1.40	1.40		0.00	1.40					
12	1.95	2.80	2.43	2.62	5.10	1	(0.28)	4.82					
13	20.30	1.98	1.90	1.94	39.38		0.00	39.38					
14	0.60	0.00	2.46	1.23	0.74		0.00	0.74					
15	20.60	2.50	2.56	2.53	52.12		0.00	52.12					
16	3.60	2.70	3.70	3.20	11.52	3	(0.84)	10.68					
17	0.94	0.00	2.50	1.25	1.18		0.00	1.18					
18	1.90	0.00	2.88	1.44	2.74		0.00	2.74					
19	2.53	1.15	1.70	1.43	3.61	1	(0.28)	3.33					
20	14.65	2.50	2.50	2.50	36.63		0.00	36.63					
21	13.10	2.50	2.42	2.46	32.23		0.00	32.23					
22	28.60	2.42	2.42	2.42	69.21	2	(0.56)	68.65					消火栓
23	27.85	1.80	1.80	1.80	50.13		0.00	50.13					
24	14.30	1.80	1.70	1.75	25.03	1	(0.28)	24.75					
25	18.40	1.70	1.70	1.70	31.28		0.00	31.28					
26	20.70	1.70	1.95	1.83	37.78	1	(0.28)	37.50					
27	21.80	1.95	1.95	1.95	42.51		0.00	42.51	4.00				
28	14.85	1.95	2.00	1.98	29.33		0.00	29.33					
29	17.25	1.90	1.90	1.90	32.78	2	(0.56)	32.22					消火栓
30	0.50	0.00	1.80	0.90	0.45		0.00	0.45					
31	13.20	1.72	1.70	1.71	22.57		0.00	22.57					
32	0.60	3.60	0.85	2.23	1.34		0.00	1.34					
33	1.60	0.85	2.00	1.43	2.28	1	(0.28)	2.00					
34	13.90	1.70	1.70	1.70	23.63		0.00	23.63					
35	2.70	2.20	3.10	2.65	7.16		0.00	7.16					
36	29.40	3.10	3.10	3.10	91.14	1	(0.28)	90.86					
37	2.20	3.10	1.20	2.15	4.73	1	(0.28)	4.45					
38	2.95	4.82	3.73	4.28	12.61	1	(0.28)	12.33					

鋪 装													
NO	面積								鋪装版切断			補足材	備考
	L	W1	W2	— W	小計	人孔蓋控除 (Φ600)		計				RM-40 t =2	
	m	m	m	m	m2	個	0.28m2/個	m2	m	m	m	m2	
39	1.80	0.00	2.94	1.47	2.65		0.00	2.65					
40	23.50	2.94	2.94	2.94	69.09		0.00	69.09					
41	1.86	2.94	4.94	3.94	7.33		0.00	7.33					
42	13.50	2.97	3.00	2.99	40.30	1	(0.28)	40.02					
43	2.02	7.62	5.64	6.63	13.39	1	(0.28)	13.11	2.80				
44	1.40	6.65	3.90	5.28	7.39		0.00	7.39					
45	30.70	3.90	3.96	3.93	120.65	1	(0.28)	120.37					
46	4.40	3.96	4.30	4.13	18.17		0.00	18.17					
47	23.30	4.00	4.12	4.06	94.60	1	(0.28)	94.32					
48	36.05	4.12	4.00	4.06	146.36	1	(0.28)	146.08	1.40				
49	10.65	4.00	4.00	4.00	42.60	1	(0.28)	42.32					消火栓
50	3.50	4.00	3.60	3.80	13.30		0.00	13.30					
51	7.90	3.60	3.60	3.60	28.44		0.00	28.44				28.44	
52	2.00	3.20	3.20	3.20	6.40		0.00	6.40				6.40	
53	2.81	3.20	2.10	2.65	7.45		0.00	7.45	3.00			7.45	
54	6.20	2.10	2.10	2.10	13.02		0.00	13.02	6.20			13.02	
55	5.20	1.80	1.80	1.80	9.36		0.00	9.36	5.20			9.36	
56	26.10	2.90	2.90	2.90	75.69		0.00	75.69				75.69	
57	34.25	2.90	2.80	2.85	97.61		0.00	97.61				97.61	
58	17.50	2.40	2.40	2.40	42.00	1	(0.28)	41.72				41.72	
59	1.20	0.00	2.40	1.20	1.44		0.00	1.44	2.70			1.44	
合計	656.22	2.74			1795.02	26	-7.28	1787.74	51.40			281.13	